

Background

The Princes Highway between Oak Flats and Dunmore was constructed in the 1930s and was no longer suitable for the traffic flows that it was required to carry. Early planning by the RTA identified a new road corridor, generally following the railway line. This new corridor was reserved in Shellharbour City Council's town plan in 1986.

On 28 February 2007 a contract was awarded to FRH Group Pty Ltd to construct the new section of the Princes Highway between Oak Flats and Dunmore.

The new highway comprised a four-lane divided carriageway, with a grade-separated interchange linked to Shellharbour Road. Shellharbour Road was also upgraded to four lanes, matching the remainder of its link to Wollongong.

The new highway links the Oak Flats Interchange to the North Kiama Bypass providing a high standard four-lane highway from Sydney to south of Kiama.

Challenge

Residents of the rapidly developing suburbs of Shellharbour required ready access to the Princess Highway as the current interchange was becoming congested and unsafe. The solution: a new interchange. The new interchange, and the lead up to it, has the additional benefit of diverting a portion of the Princes Highway that previously had a number of sharp bends and consequently was a potentially dangerous section of the highway. The Roads and Traffic Authority (RTA) provided a detailed specification pertaining to the architectural finish on the facing panels for the Reinforced Earth® walls required for various structures within the interchange. A Vine Pattern finish as seen on another project (Carramar) was proposed for the majority of the wall. The challenge lay in developing three different types of additional feature panels - two of which incorporated shell designs and the other being the Shellharbour Council's emblem itself.

Solution

The new interchange incorporates four bridge abutments, two of which are used to form a rail over pass and another two for a road overpass. The design of the rail overpass incorporates provision for a future railway station too. The Reinforced Earth Company (RECO) was appointed to design and supply a total of 3141m² of Reinforced Earth® walls for this project.

CASE STUDY

Oak Flats South Coast, NSW, Australia

Reinforced Earth® Walls TerraSet®

Owner:	Roads and Traffic Authority
Consultants:	Roads and Traffic
Contractor:	Authority FRH Group Pty Ltd
Construction:	2008





Main and Top: Vine Pattern, Shell Pattern and Shell Harbour Council Emblem uniquely detailed TerraSet® panels.

Above: Preparation of panel mould for Vine Pattern Finish.



ransport infrastructure



RECO worked closely with project architects and sculptors running through several design iterations during the progressive development of the exact panel finish required by the RTA and Fulton Hogan. The end result was two individual shell patterns and one Shellharbour Council emblem itself.

Special features/benefits

- There are numerous benefits

 of the new interchange:
 Significant reduction in traffic
 congestion; improved traffic
 flow; improved safety with the
 elimination of a narrow winding
 alignment which was
 completely devoid of
 overtaking opportunities; the
 elimination of delays at the
 Shellharbour Road and
 Princes Highway junction; a
 flood free route and reduced
 delays caused by the train
 crossing.
- Besides structural, construction efficiency and budgeting benefits, Reinforced Earth® structures also offer limitless aesthetic and architectural possibilities. When Reinforced Earth® is specified or selected in the earliest phases of a project, specialists from RECO can help owners, their engineers and architects to maximize the design possibilities, allowing architectural treatments to be easily accommodated. At RECO we continue to innovate in collaboration with our clients in order to offer the widest possibilities of architectural expression together with the assurance of Reinforced Earth Quality.



Left: Overview of the Bridge Abutment on the road overpass

Top and Below: Close up of the feature panels and their placement within the Reinforced Earth® walls

Project specifications

System	TerraSet®
Finish	Vine Pattern Feature Panels
Structure	Bridge Abutments
Area	3141m²
Max. Height	10.77m
Length	620m (total)
Design load	25kPa
Design life	100 years





Reinforced Earth Pty Limited Level 4, 20 George Street Hornsby NSW 2077 Australia Ph +61 2 9910 9910 Fax +61 2 9910 9999 www.reco.com.au

Reinforced Earth Limited

PO Box 72 734 Papakura Auckland New Zealand Ph +64 9 236 3385 Fax +64 9 236 3385 www.reco.com.au

